CASE STUDY / PANAMAX / SECURITY & COMMUNICATIONS

Secure spaces. Connected people.

Panamax Infotech Limited

Ahmedabad | Office infrastructure

Matrix CCTV and access control supply, installation and existing-system integration, complemented by a 500-line EPABX installation scope.

MATRIX SECURITY

CCTV + two-door access control

500-LINE EPABX

Enterprise voice installation scope



Company photograph supplied by D-TECH.

Project context | Integrating security and communications

Panamax required supplied security equipment to integrate and operate with its existing systems. D-TECH's scope combines equipment supply, CCTV and door-system installation, commissioning and comprehensive support. The 500-line EPABX element supplied for this case study extends the solution narrative to office communications, with capacity, extension mapping and call-routing design addressed during implementation.

Scope	Documented baseline / engagement detail
CCTV supply	PO PIL/PO/14-15/29: 10 Matrix SATATYA 600 TVL analogue dome cameras; 1 DVR8S 8-channel DVR; 2 TB and 4 TB HDDs; 4 camera power supplies; 20 BNC + DC pin sets.
Door access control	2 COSEC door FOP units with HID iCLASS; 2 PATH RDFI fingerprint / HID readers; 1 HID iCLASS module for an existing system; 2 electromagnetic locks.
Installation & support	WO PIL/WO/14-15/003: 18 CCTV installation charge units and 2 door installation units. Both orders require existing-system integration and one-year comprehensive support.
Enterprise telephony	500-line EPABX installation stated by D-TECH. PBX model, extension types, trunks, licences and distribution schedule are not specified in the attached orders.

Order references dated 22 December 2014. Historical customer: Panamax Infotech Limited; supplier named D-TECH Computers.

Document guide: 03 Security architecture | 04 EPABX design | 05 Installation & testing | 06 Support & customer details.

LOGICAL DRAWING / EXISTING-SYSTEM INTEGRATION / SEPARATE SERVICE PATHS

Security architecture | Video and controlled entry

CCTV provides recorded visual evidence; access control governs door entry. The two systems retain their own operating paths and records. Any event correlation or software integration requires confirmation of the installed interfaces.

CAMERA FIELD LAYER

Analogue dome cameras
Camera power supplies
BNC video + DC connections

→

DVR & RECORDING

SATATYA DVR8S
Disk compatibility / allocation check
Channel mapping and recording schedule

→

SECURITY OPERATOR

Live view, playback and
authorised evidence export

CREDENTIAL / READER

Fingerprint / HID iCLASS
Door-side readers
Enrolment and access permissions

→

COSEC DOOR CONTROL

Two-door installation
Credential validation and lock control
Existing-system interface verification

→

LOCK & ACCESS RECORD

2 electromagnetic locks
Approved exit / emergency release
Access logs where supported

Reconcile 10 supplied cameras against the listed 8-channel DVR and existing recorder capacity. The WO’s 18 charge units do not prove 18 cameras.

CONCEPTUAL VOICE DESIGN / CAPACITY & TRUNK SIZING / EXTENSION MANAGEMENT

Enterprise telephony | 500-line EPABX installation

The EPABX design links office users through a central exchange, with an approved extension plan, inbound / outbound routing and class-of-service controls. The 500-line scope must be defined as installed extension capacity versus active users; it does not establish 500 simultaneous external calls.

SERVICE PROVIDER

Approved external voice trunks
Interface and carrier handoff
Concurrent call sizing

CENTRAL EPABX

500-line installation scope
Extension / trunk provisioning
Route and permission configuration

OFFICE EXTENSIONS

Department / floor numbering
Analogue, digital or IP endpoints
Type confirmed during survey

PHYSICAL DISTRIBUTION

Rack, power and earthing checks
MDF / patching for wired extensions
Labelled termination and cable tests

CALL CONTROLS

Reception and call-transfer tests
Inbound / outbound route validation
Restrictions and emergency routing

OPERATIONS HANDOVER

Approved extension directory
Configuration copy and access control
Operator training and fault reporting

Feature availability depends on the selected PBX and licences. IP endpoints additionally require verified LAN / PoE capacity and voice QoS design.

Implementation | Survey to operational handover

01 | SURVEY & DESIGN

Confirm existing CCTV channels, two-door hardware, PBX capacity, trunks, cabling and site access.

02 | PREPARE & INSTALL

Label cables, mount cameras, fit readers / locks and install EPABX hardware with approved power.

03 | CONFIGURE

Map channels / recording; enrol credentials; provision extensions, trunks and call permissions.

04 | INTEGRATE

Verify existing-system operation and interfaces; apply approved changes with rollback copies.

05 | TEST & ACCEPT

Test image / playback, authorised entry / denial / exit, and inbound / outbound / transfer calls.

06 | HAND OVER

Submit asset and extension schedules, configuration copies, test records and operator guidance.

Acceptance checklist: recording / playback | door release and safe exit | extension-to-extension calls | trunk routing | customer sign-off.

Customer care | Coordinated support across systems

CUSTOMER & PROJECT REFERENCE

Panamax Infotech Limited
Order delivery address: 8 Floor, 615, J B Tower,
beside SAL Hospital, Thaltej Cross Road,
Ahmedabad, Gujarat.
PO / WO dated 22 December 2014.

D-TECH VALUE

One delivery interface for supply and installation; compatibility checks with existing systems; structured testing; coordinated CCTV, access and voice fault diagnosis; documented handover.

Support stage	Service approach
Report -> diagnose	Identify system, location and impact. Separate camera / DVR faults, reader / lock faults and extension / trunk faults.
Restore -> verify -> close	Coordinate approved corrective work, test the affected service with the customer and record the action, test results and closure.

D-TECH Customer Care | support.dtechindia.com | +91 99989 03042

Sources: supplied 2014 PO / WO and company images; EPABX 500-line scope supplied by D-TECH. Diagrams explain the delivery method.
Order support term: one year comprehensive. No ongoing AMC term, achieved SLA, uptime or completed EPABX test record was supplied.