Surveillance care. Planned maintenance. Structured response.

Sun Pharmaceutical Industries Limited

Dahej API SEZ Plant | Gujarat

CCTV system service, repair, covered spares and technical support with a documented maintenance and fault-resolution process.

COMPREHENSIVE CCTV CARE

Latest supplied CAMC period: 01 June 2026 - 31 May 2027



Site photograph supplied by D-TECH

CUSTOMER REQUIREMENT / CONTRACT REFERENCE / EQUIPMENT BASELINE

Engagement | A documented CCTV maintenance scope

Sun Pharma’s Dahej API SEZ CCTV contracts define preventive maintenance, service and repair alongside telephonic technical assistance. The service approach covers the full fault path: camera, power, network, recorder and storage, followed by a documented verification and customer handover.

Record	Documented scope / period	Case-study use
PO 5000298980 15 December 2023	31 cameras described: boundary wall 28, canteen 2 and warehouse 1, with accessories; comprehensive maintenance.	Earlier scope reference; avoid treating it as an additional current fleet.
PO 5000366364 28 February 2025	01 March 2025 - 28 February 2026. Quarterly PM visits, breakdown visits, telephonic support, FOC spares / consumables and protocol-based reports.	Detailed equipment and service baseline; actual site records establish delivery and maintenance results.
PO 5000452536 13 July 2026	01 June 2026 - 31 May 2027 CAMC; explicitly references PO 5000366364.	Latest supplied contract reference. Live inventory and applicable work plan to be reconciled with the customer.

DOCUMENT GUIDE

03 Covered system & diagnostics | 04 Illustrated service-response flow | 05 Preventive maintenance & reports | 06 Customer care & handover

This case study presents contracted scope and a delivery methodology. No uptime, response achievement or ticket-volume metrics were supplied.

System care | Diagnose the entire surveillance path

CAMERA LAYER

2025 list: 31 standard cameras + 10 explosion-proof cameras. Check channel, lens, condition and approved power.

NETWORK / POWER

PoE switches, SFP modules, fibre LIUs / joints, camera adaptors and patching. Check link and power health.

RECORDING / DISK

Listed 32-channel NVR and 4 x 6TB surveillance HDDs. Verify channels, disk health and playback.

Diagnostic symptom	Service sequence / evidence
CAMERA OFFLINE	Confirm affected channel, camera power / adaptor or PoE, link status, patching and device health before replacement.
VIDEO / PLAYBACK ISSUE	Check live image, recorder time, recording schedule, stream status, disk alerts and representative playback; record findings.
PARTS / RECONFIGURATION	Identify the covered failed component, arrange contract-covered spares, preserve authorised configuration and retest the complete path.

41 listed cameras and one listed 32-channel NVR do not establish the live channel allocation. Reconcile recorder capacity / mapping; do not assume all cameras use one NVR.

Service response | From reported fault to confirmed closure

01 | REPORT

Log location, asset / channel, symptom, impact and contact details.

02 | TRIAGE

Check camera, power, network, recorder and storage; identify the affected component.

03 | PLAN

Agree site access and corrective action; route specialist / OEM help if needed.

04 | RESTORE

Repair / replace covered parts and perform approved configuration recovery.

05 | VERIFY

Prove live video, recording, timestamp and representative playback with the customer.

06 | CLOSE

Document the action, replaced parts, tests and customer confirmation; track recurring faults.

Raise a service request | support.dtechindia.com ↗ | +91 99989 03042

Preventive maintenance | Consistent checks and reporting

Control	Contract basis and recommended service evidence
PLANNED SERVICE	2025 PO specifies 4 quarterly PM visits per year, breakdown visits and telephonic support. Validate the applicable 2026-27 schedule against the referenced scope and customer plan.
CAMERA / SITE CHECK	Record image and physical condition, connection / power issues and access constraints. Follow plant safety procedures; service explosion-proof units through approved methods that preserve certified integrity.
NETWORK / RECORDING CHECK	Check PoE / link status, fibre and patching, recorder alarms, disk status, time and sample recordings. Capture failures and corrective actions by asset / channel.
SPARES / TOOLS	2025 scope puts replacement spares and servicing consumables on an FOC basis and includes service tools, measurement and diagnostic equipment in vendor scope. Apply the actual covered inventory.
QUALIFICATION / REPORTS	Carry out qualification and generate reports using Sun Pharma’s supplied protocols. Submit the annual performance test report to the concerned site engineer as specified in the 2025 PO.

RESPONSE AND RESTORATION GOVERNANCE

The supplied CCTV scopes do not define a fixed response / restoration time in hours. Record timestamps and agree incident priorities, update intervals and targets with the site owner; do not imply an unsupported numeric SLA.

Technical maintenance does not by itself establish pharmaceutical validation or regulatory compliance. Protocol completion requires customer review and records.

Customer care | Clear ownership and service records

CUSTOMER & LOCATION

Sun Pharmaceutical Industries Ltd.
Dahej API SEZ Plant
Z/15, Dahej SEZ Ltd., Taluko Vagra,
Bharuch 392130, Gujarat, India.
Latest PO: 5000452536 dated 13 July 2026.

SERVICE HANDOVER PACK

Asset / channel mapping, covered-equipment register, approved PM plan, protocol-based reports, fault and parts records, configuration copies, playback checks and open-action ownership.



SUPPLIED FACILITY VIEW

D-TECH | CUSTOMER SUPPORT

support.dtechindia.com | Raise ticket ↗

+91 99989 03042

Sources: supplied POs 5000298980, 5000366364 and 5000452536. Latest contract period: 01 June 2026 - 31 May 2027.

Equipment quantities describe the 2025 order baseline. Service achievements, live inventory changes and completed test results require project records.